

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2013-14/RD/WORK_INDENT 9289/call-2

APPROVED SCHEDULE - B

Tender Notification No: No.EE/BTP/BBMP/E-PMT/16/2013-14, Date: 06.12.2013

Providing Street Light (MV/ SV) and Switch board in Ward No. 11 (Kuvempunagara), Vidyanarayapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				GANGADHAR H	
				In Figures	In Words
1	268	Supplying High pressure sodium vapour street light fitting die cast aluminium canopy with aluminium housing for control gear, finished stove enamel gray glassy white canopy interior with a pair of anodized aluminium reflectors with toughened flat glass, gasket lining for drip insect resistance duly wired with porcelain holder copper choke, igniter and HPF condenser including a sodium vapour lamp .II 250 Watts a) Group 'A' etc complete as per specifications and directions of engineer in charge of the work.	Cum	6088.5	Rupees Six Thousand Eighty Eight and Fifty Paise Only
2	268	Supplying & fixing mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 or rail or RCC pole/wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires complete. b) Using 32mm dia G.I pipe etc complete as per specifications and directions of engineer in charge of the work.	Cum	678.15	Rupees Six Hundred Seventy Eight and Fifteen Paise Only
3	90	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanized, steel wire/steel tap armoured cable with PVC outer sheathing 1.1KV Class I. Class 'A' PVC Cable d) 4 core 16sqmm etc complete as per specifications and directions of engineer in charge of the work.	Cum	148.5	Rupees One Hundred Forty Eight and Fifty Paise Only
4	90	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe/ stoneware pipe/ on wall/ on pole as required .II. On wall /Structure a) 6 sqmm to 16sqmm etc complete as per specifications and directions of engineer in charge of the work.	Cum	17.82	Rupees Seventeen and Eighty Two Paise Only
5	100	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes f) 16 sqmm etc complete as per specifications and directions of engineer in charge of the work.	Cum	13.86	Rupees Thirteen and Eighty Six Paise Only
6	18	Supplying and fixing Moulded Case Circuit Breaker (MCCB) Over the existing wood/panel board using necessary screws, bolts, nuts and wiring thermal Magnetci Microprocessed release and Earth Fault as per IS-13947. (Icu=Ics) THREE POLE a) 100 Amps 25 kA, 2) Group 'B' etc complete as per specifications and directions of engineer in charge of the work.	Cum	3425.4	Rupees Three Thousand Four Hundred Twenty Five and Forty Paise Only


Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

7	✓ 18	Supply and Installation/Fixing/Provision for mounting of HRC Fuse /MCB with suitable connector/terminal for 3 Ph/1 Ph connections with Loop-in & Loop-Out terminals for 10 Sqmm/25 sqmm 3.5 C Al/AR/Cu/AR Cable and branchout 2.5 Sqmm 2 Core Al/Cu PVC insulated cable, enclosure, which should be shock proof, safe IP 65 (Weather Proof), rust proof, dust proof, water proof having Internally Embedded Gasket with provision for cable entry through IP 65 Thermoplastic, Polyamide glands and /or grommets. a) 200x200x98mm etc complete as per specifications and directions of engineer in charge of the work.	Cum	✓ 915.75	Rupees Nine Hundred Fifteen and Seventy Five Paise Only
8	✓ 400	Wiring for lighting/power circuit using one of PVC insulated 1100v grade, multistrand Aluminium conductor single core cable in open or consealed system of wiring. I Group A Materials. e) 10 sqmm etc complete as per specifications and directions of engineer in charge of the work.	Cum	✓ 22.77	Rupees Twenty Two and Seventy Seven Paise Only
9	✓ 60	Supply and fixing of backlite D.P/Socket/switch with/without neon indicator over existing wood board or flush mounting in plastic plates/nitches. I Using Group 'A' Material. a) 32Amps Flush/project type DP switch etc complete as per specifications and directions of engineer in charge of the work.	Qtl	✓ 143.55	Rupees One Hundred Forty Three and Fifty Five Paise Only
10	✓ 60	Supplying and flush mounting teak wooden box without front plant made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete.b) 12"x9"x3" (300x228x76mm) etc complete as per specifications and directions of engineer in charge of the work.	Sqm	✓ 79.2	Rupees Seventy Nine and Twenty Paise Only

Signature of the Contractor 


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92